



## Fire Protection Contractor QA/QC Plan Sample

Selected pages (not a complete plan)

- QA/QC Plan Sample
- Project-Specific Quality Plan
- Quality Manual
- Fire Protection Standards & Inspection Forms

**Contact:**  
**Ed Caldeira**  
**410-451-8006**

Questions? Call Ed Caldeira 410-451-8006



# Quality Assurance/Quality Control Plan

[ProjectName]

[ProjectNumber]

Version Date: September 14, 2011

# PROJECT-SPECIFIC FIRE PROTECTION QUALITY PLAN

## TABLE OF CONTENTS

<b>Background Information</b> .....	<b>7</b>
Project Name .....	7
Project Number .....	7
Project Location.....	7
Project Description .....	7
Project Scope.....	7
<b>A. [CompanyName] Quality Policy</b> .....	<b>8</b>
<b>B. Key Elements of the Fire Protection Quality Plan</b> .....	<b>9</b>
Project Quality Assurance/Quality Control Plan Overview .....	12
<b>C. Project Quality Coordination and Communication</b> .....	<b>13</b>
<b>D. Project QC Personnel</b> .....	<b>17</b>
Project QC Job Position Assignments .....	17
Project QC Organization Chart .....	18
<b>E. Duties, Responsibilities, and Authority of QC Personnel</b> .....	<b>19</b>
<b>F. Personnel Qualifications and Technical Certifications</b> .....	<b>25</b>
Personnel Certification Requirements .....	25
<b>G. Qualification of Third Party Inspection/Testing Companies and Subcontractors And Suppliers</b> .....	<b>27</b>
Fire Protection Inspection/Testing Laboratory Qualification Requirements.....	27
Qualification .....	27
Purchase Order Approval .....	28
<b>H. Quality Training</b> .....	<b>30</b>
<b>I. Fire Protection Project Quality Specifications</b> .....	<b>33</b>
Compliance with Industry Fire Protection Standards.....	33
<b>J. Design Control</b> .....	<b>35</b>
<b>K. Material Inspection Traceability and Quality Controls</b> .....	<b>36</b>
Identification of Lot Controlled Materials .....	36
Material Receiving and Inspection .....	36
<b>L. Fire Protection Inspection and Test Plan</b> .....	<b>41</b>
Inspection and Testing Fire Protection Standards.....	41
Control of Inspection, Measuring, and Test Equipment.....	41
<b>M. Fire Protection Work Task Quality Inspections</b> .....	<b>44</b>
Identification of Quality Inspected Fire Protection Work Tasks .....	44
Required Inspections For Each Fire Protection Work Task.....	44
Daily Quality Control Report.....	45

<b>N. Control of Punch Items and Nonconformances</b> .....	<b>49</b>
Marking of Nonconformances and Observations.....	49
Control the Continuation of Work.....	49
Recording of Nonconformances .....	49
Quality Manager Disposition of Nonconformance Reports .....	50
Corrective Actions .....	50
Nonconformance Preventive Actions.....	51
<b>O. Project Completion Inspections</b> .....	<b>53</b>
Punch-Out QC Inspection .....	53
Pre-Final Customer Inspection .....	53
Final Acceptance Customer Inspection .....	54
<b>P. Project Quality Records and Documents</b> .....	<b>57</b>
<b>Q. Quality Assurance Surveillance</b> .....	<b>60</b>
Project Quality Performance Surveillance.....	60
Project Quality Audits.....	60
Project Audit Plan .....	61
Project Audit Requirements .....	61
<b>R. Additional Quality Control Requirements</b> .....	<b>63</b>

Selected Pages

## M. FIRE PROTECTION WORK TASK QUALITY INSPECTIONS

[CompanyName] identifies a list of work tasks, phases of production, which will be quality controlled. Each work task is subject to a series of inspections; before, during, and after the work is complete. Each inspection verifies compliance with full scope of the relevant specifications; not limited to checkpoints for heightened awareness.

The initial task-ready inspection occurs when crews are ready to start work and ensures that work begins only when it does not adversely impact quality results.

Incoming material inspections verify that materials are as specified and meet all requirements necessary to assure quality results.

Work-in-process inspections continuously verify that work conforms to project specifications and workmanship expectations. Work continues only when it does not adversely impact quality results.

At completion of the work task an inspection verifies that work, materials, and tests have been completed in accordance with project quality requirements. When appropriate, functional tests are performed.

Inspection results are recoded and maintained as part of the project files.

The Quality Manager identifies each Task that is a phase of construction that requires separate quality controls to assure and control quality results. Each Task triggers a set of requirements for quality control inspections before, during and after work tasks.

Independent quality audits are conducted to verify that the task quality controls are operating effectively.

Construction projects may execute a work task multiple times in a project, in which case a series of quality inspections are required for each work task.

Independent quality control audits are conducted to verify that the task quality controls are operating effectively.

### IDENTIFICATION OF QUALITY INSPECTED FIRE PROTECTION WORK TASKS

A listing of project work tasks is included on the Quality Control work task List and included as an exhibit in this subsection.

### REQUIRED INSPECTIONS FOR EACH FIRE PROTECTION WORK TASK

Each work task is subject to a series of inspections before, during, and at completion including:

- Preparatory site inspection
- Material inspections
- Work task-ready inspections
- Work in process inspections
- Work task Completion inspections

Results of inspections will be recorded as follows:

- Task inspection results will be recorded on the Work task Inspection Form.
- Daily inspections of work in process will be recorded on the Daily Quality Control Report.

Each item is described below.

### **PREPARATORY SITE INSPECTION**

The Superintendent performs a quality inspection of the work area and:

- Assesses completion of required prior work
- Verifies field measurements
- Assures availability and receiving quality inspection status of required materials
- Identifies any nonconformances to the requirements for the task to begin
- Identifies potential problems

### **TASK-READY INSPECTIONS**

For each work task, the Superintendent or a qualified inspector performs job-ready quality inspections to ensure that work activities begin only when they should begin. Job-ready quality inspections verify that conditions conform to the project quality requirements.

### **WORK IN PROCESS QUALITY INSPECTIONS**

For each work task, the Superintendent or a qualified inspector performs an initial work in process inspection when the first representative portion of a work activity is completed.

The Superintendent or a qualified inspector performs ongoing work in process quality inspections to ensure that work activities continue to conform to project quality requirements.

### **WORK TASK COMPLETION QUALITY INSPECTIONS**

For each work task, the Quality Manager or a qualified inspector inspects the completion of each work task to verify that work conforms to project quality requirements.

Completion quality inspections are performed for each work task. Completion quality inspections are conducted before starting other work activities that may interfere with an inspection.

Any outstanding punch items remaining after the work task completion inspection is deemed a nonconformance.

<b>[CompanyName]</b> <b>Quality Inspection and Test Plan</b>											
CONTRACT NUMBER				PROJECT NAME				CONTRACTOR			
[ProjectNumber]				[ProjectName]				[CompanyName]			
SPECIFICATION SECTION AND PARAGRAPH NUMBER	SCHEDULE ACTIVITY ID	TEST REQUIRED	ACCREDITED/ APPROVED LAB YES /NO	SAMPLED BY	TESTED BY	LOCATION OF TEST ON/OFF SITE/SITE	DATE COMPLETED	DATE FORWARDED TO CUSTOMER	REMARKS		

Selected Pages

## N. CONTROL OF PUNCH ITEMS AND NONCONFORMANCES

Should a problem occur in the quality of work, we systematically contain the issue and quickly make corrections. Our first action is to clearly mark the item by tape, tag, or other easily observable signal to prevent inadvertent cover-up.

Then we expedite a corrective action that brings the workmanship or material issue into conformance by repair, replacement, or rework. Previously completed work is reinspected for similar nonconformances. In the event that we cannot correct the item to meet contract specifications, the customer will be notified and customer approval of corrective actions is required before proceeding.

Fixing problems found is not sufficient. [CompanyName] systematically prevents recurrences to improve quality. First enhanced controls and management monitoring are put into place to assure work proceeds without incident. Then using a structured problem solving process, [CompanyName] identifies root causes and initiates solutions. Solutions may involve a combination of enhanced process controls, training, upgrading of personnel qualifications, improved processes, and/or the use of higher-grade materials. Follow-up ensures that a problem is completely resolved. If problems remain, the process is repeated.

Nonconformances and their resolution are recorded on a Nonconformance Report form. A Nonconformance Report form exhibit is included in this subsection.

### MARKING OF NONCONFORMANCES AND OBSERVATIONS

When the Quality Manager, Superintendent, inspector, or customer identifies a nonconformance or an observation, the item is quickly and clearly marked by paint, tape, tag, or other easily observable signal to prevent inadvertent cover-up.

### CONTROL THE CONTINUATION OF WORK

After the item is marked, the Superintendent determines if work can continue in the affected area:

**CONTINUE WORK:** When continuing work does not adversely affect quality or hide the defect, work may continue in the affected area while the disposition of the item is resolved. The Superintendent may place limitations on the continuation of work.

**STOP WORK ORDER:** When continuing work can adversely affect quality or hide the defect, work must stop in the affected area until the disposition of the item resolved. The Superintendent identifies the limits of the affected area. The Superintendent quickly and clearly marks the stop work area.

### RECORDING OF NONCONFORMANCES

If nonconformances or observed items exist by the work task completion inspection, the Superintendent or inspector records the nonconformances on a nonconformance report.

The Superintendent sends the nonconformance report to the Quality Manager.



<b>[CompanyName]</b> <b>Nonconformance Report</b> <small>Version July 17, 2012</small>		
Nonconformance Report Control ID	Project ID	Project Name
	[ProjectNumber]	[ProjectName]
Preparer Signature/ Submit Date		Quality Manager Signature / Disposition Date
Description of the requirement or specification		
Description of the nonconformance, location, affected area, and marking		
Disposition	<input type="checkbox"/> Replace <input type="checkbox"/> Repair <input type="checkbox"/> Rework <input type="checkbox"/> Use As-is	
	Approval of disposition required by customer representative? Yes <input type="checkbox"/> No <input type="checkbox"/>	
	Customer approval signature /date: _____	
Corrective Actions	<input type="checkbox"/> Corrective actions completed Name/Date: _____	
	Customer acceptance of corrective actions required? Yes <input type="checkbox"/> No <input type="checkbox"/>	
	Name/Date: _____	
Preventive Actions	<input type="checkbox"/> Preventive actions completed Name/Date: _____	

Selected Pages

# QUALITY MANUAL

## TABLE OF CONTENTS

<b>1. Quality System Management and Responsibilities</b> .....	<b>7</b>
1.1. Overview.....	7
1.2. [CompanyName] Quality Policy.....	7
1.3. Quality Duties, Responsibilities, and Authority.....	7
1.4. Quality System Performance Measures.....	10
1.5. Customer Satisfaction Performance Measures.....	10
1.6. Exceptions.....	10
<b>2. Project Quality Assurance/Quality Control Plan</b> .....	<b>11</b>
2.1. Overview.....	11
2.2. [CompanyName] Project License and Qualification Requirements.....	11
2.3. Project Personnel and Qualifications.....	11
2.4. Project Quality Assurance/Quality Control Plan.....	12
2.5. Identification of Quality Controlled Work Tasks.....	13
2.6. Project Quality Inspection and Test Plan.....	13
2.7. Project Quality Communications Plan.....	13
2.8. Project Quality Training Plan.....	13
2.9. Customer Training On Operation And Maintenance.....	13
2.10. Project Records and Documentation Plan.....	13
2.11. Project Audit Plan.....	14
<b>3. Contract Specifications</b> .....	<b>15</b>
3.1. Overview.....	15
3.2. Contract Technical Specifications.....	15
3.3. Contract Drawings.....	15
3.4. Contract Submittals.....	15
3.5. Customer Submittal Approval.....	17
3.6. Contract Warranty.....	17
3.7. Contract Review and Approval.....	18
<b>4. Design Control</b> .....	<b>19</b>
4.1. Overview.....	19
4.2. Design Input Review.....	19
4.3. Project Design Quality Assurance/Quality Control Plan.....	19
4.4. Design Progress Reviews.....	20
4.5. Design Output Verification and Approval.....	20
<b>5. Project-Specific Quality Standards</b> .....	<b>21</b>
5.1. Overview.....	21
5.2. Regulatory Codes.....	21

5.3. Industry Quality Standards .....	21
5.4. Material and Equipment Specifications.....	21
5.5. Work Process Specifications.....	22
5.6. Controlled Material Identification and Traceability .....	22
5.7. Measuring Device Control and Calibration.....	23
5.8. [CompanyName] Quality Standards .....	23
5.9. Application of Multiple Sources of Specifications .....	23
<b>6. Project Purchasing .....</b>	<b>24</b>
6.1. Overview.....	24
6.2. Qualification of Outside Organizations and Company Departments .....	24
6.3. Quality Responsibilities of Key Subcontractor Personnel.....	25
6.4. Requirements for Subcontractor QC Plan .....	26
6.5. subcontractor and supplier Quality Policy.....	26
6.6. Project subcontractor and supplier List.....	27
6.7. Purchase Order Requirements .....	27
6.8. Project Purchase Order Approvals.....	27
<b>7. Process Controls.....</b>	<b>29</b>
7.1. Overview.....	29
7.2. Project Startup and Quality Control Coordination Meeting .....	29
7.3. Preparatory Project Quality Assurance/Quality Control Plan Planning.....	29
7.4. Weekly Quality Planning and Coordination Meetings.....	30
7.5. Process Control Standards.....	30
7.6. Daily Quality Control Report.....	31
7.7. Monthly Quality Control Report .....	32
<b>8. Inspections and Tests .....</b>	<b>33</b>
8.1. Overview.....	33
8.2. Required Work Task Quality Inspections and Tests.....	33
8.3. Additional Inspection Requirements for Process Tasks.....	34
8.4. Inspection of Special Processes .....	34
8.5. Independent Measurement and Tests .....	35
8.6. Commissioning Functional Acceptance Tests.....	35
8.7. Hold Points for Customer Inspection.....	35
8.8. Quality Inspection and Test Specifications .....	35
8.9. Inspection And Test Acceptance Criteria.....	35
8.10. Inspection and Test Status.....	36
8.11. Independent Quality Assurance Inspections .....	36
8.12. Inspection and Test Records.....	36
8.13. Project Completion and Closeout Inspection .....	37
<b>9. Nonconformances and Corrective Actions .....</b>	<b>39</b>
9.1. Overview.....	39
9.2. Nonconformances .....	39
9.3. Corrective Actions .....	40

<b>10. Preventive Actions .....</b>	<b>41</b>
10.1. Overview.....	41
10.2. Identify Preventive Actions for Improvement .....	41
10.3. Train Preventive Actions for Improvement .....	41
<b>11. Quality System Audits .....</b>	<b>43</b>
11.1. Overview.....	43
11.2. Project Quality System Audit.....	43
11.3. Company-wide Quality System Audit .....	43
<b>12. Record and Document Controls.....</b>	<b>44</b>
12.1. Overview.....	44
12.2. Quality System Documents .....	44
12.3. Document Controls.....	44
12.4. Record Controls .....	45
<b>13. Appendix.....</b>	<b>47</b>
13.1. Definitions of Terms .....	47

Selected Pages

## 7. PROCESS CONTROLS

### HOW WORK IS CARRIED OUT

#### 7.1. OVERVIEW

The painting process plan defines how project work is to be done and approved for the overall project. The painting process plan is communicated to all key personnel, subcontractors and suppliers in a startup meeting. As the project proceeds, work task plans provide additional details of how each individual work task is carried out. Work tasks planning meetings are used to communicate expectations of the work task plan to key personnel responsible for carrying out the work task.

#### 7.2. PROJECT STARTUP AND QUALITY CONTROL COORDINATION MEETING

Prior to the commencement of work, the Project Manager holds a meeting to discuss and coordinate how project work will be performed and controlled. Key personnel from [CompanyName], subcontractors and suppliers meet to review expectations for project quality results as well as quality assurance and quality control policies and procedures including:

- Key requirements of the project
- The Project Quality Assurance/Quality Control Plan
- Required quality inspections and tests
- The project submittal schedule
- Quality policies and heightened awareness of critical quality requirements
- Project organization chart and job responsibilities
- Methods of communication and contact information
- Location of project documents and records

#### 7.3. PREPARATORY PROJECT QUALITY ASSURANCE/QUALITY CONTROL PLAN PLANNING

##### 7.3.1. WORK TASK REQUIREMENTS REVIEW

In preparation for the start of an upcoming work task, the Superintendent reviews an integrated and coordinated set of documents that collectively define quality requirements for the work task including:

- Objectives and acceptance criteria of the work task
- Quality standards that apply to the work task
- Work instructions, process steps, and product installation instructions that apply to the work task
- Shop drawings
- Submittals
- Tools and equipment necessary to perform the work
- License, certification, or other qualification requirements of personnel assigned to work
- Required records of the process and resulting product
- The subcontractor contracted to perform the work, if applicable
- Customer contract requirements
- Required quality inspections and tests
- Method for clearly marking nonconformances to prevent inadvertent use
- Location of quality system records and documents
- Personnel training

### 7.3.2. PREPARATORY SITE INSPECTION

The Superintendent also performs a quality inspection of the work area and:

- Assesses completion of required prior work
- Verifies field measurements
- Assures availability and receiving quality inspection status of required materials
- Identifies any nonconformances to the requirements for the work task to begin
- Identifies potential problems

### 7.3.3. WORK TASK PREPARATORY QUALITY PLANNING MEETINGS

Prior to the start of a work task, the Superintendent conducts a meeting with key company, subcontractor personnel responsible for carrying out, supervising, or inspecting the work, and interested customer representatives.

During the meeting, the Superintendent communicates the work task quality requirements and reinforces heightened awareness for critical requirements. Topics for a work task quality plan meeting include:

- Work tasks quality requirements as identified in section 7.3.1
- Findings of the work task preparatory quality inspection in section 7.3.2
- Conflicts that need resolution
- Required quality documents and a verification of availability to personnel carrying out, supervising, or inspecting the work task
- Record keeping requirements and the availability of necessary forms
- Review methods and sequences of installation
- Special details and conditions
- Standards of workmanship
- Heightened awareness of critical quality requirements
- Quality risks
- Work tasks quality inspection form

# LIST OF INCLUDED INSPECTION FORMS FOR FIRE PROTECTION

## FROM CSI DIVISIONS

- Fire Suppression - 21
- Plumbing - 22
- Utilities – 33

## FORMS:

- Suppression Water Service Piping
- Fire Pumps
- Fire-Suppression Sprinkler Systems
- Fire-Suppression Standpipes
- Fire-Suppression Water Storage
- Facility Water Distribution
- Plumbing Insulation
- Water Utility Distribution Equipment

Selected Pages

## Fire Suppression-Facility Fire-Suppression Water-Service Piping 21.11.00

Project:	Phase:	Contract#:	Vendor: <b>9101</b> Field Operations	Crew:
----------	--------	------------	--------------------------------------------	-------

**Compliance Verification**

- Compliance with initial job-ready requirements
- Compliance with material inspection and tests
- Compliance with work in process first article inspection requirements
- Compliance with work in process inspection requirements
- Compliance with Task completion inspection requirements
- Compliance with inspection and test plan
- Compliance with safety policies and procedures

Reported Nonconformances and incomplete items:

**FTQ 2TQ Heightened Awareness Checkpoints**

- Piping pitched to allow complete drainage **1274**
- Piping not placed above electrical panels or switchgear **1275**
- Firestops installed at penetrations through fire partitions// fire walls// smoke partitions// or floors **1276**
- Penetrations through floor// exterior wall and roof sealed and made watertight **1277**
- Piping secured to prevent movement and chafe **1278**
- Piping bends and fittings restrained **1279**
- System pressure tested and without leaks **1280**
- Valves provided with tamper-proof seals **1281**
- Wet piping not exposed to freezing conditions **1282**
- Fire department connection type verified with Local Fire Department prior to product ordering and installation **1283**

### FTQ Scores and Completion Sign-off

**Field Mgmt.-Superintendent Inspection 91.45.01**

Quality     5   4   3   2   1   Notes:

-----

On-Time     5   4   3   2   1   Notes:

-----

Safety     5   4   3   2   1   Notes:

-----

Sign and date\*: Cell # / ID #: \_\_\_\_\_ Signed: \_\_\_\_\_ Date: \_\_\_\_\_

Task has been verified complete and in compliance with contract drawings and specifications except for non-conformances and incomplete items reported above.

**Field Mgmt.-QA Inspection 91.45.02**

Quality     5   4   3   2   1   Notes:

-----

Sign and date\*: Cell # / ID #: \_\_\_\_\_ Signed: \_\_\_\_\_ Date: \_\_\_\_\_

Task has been verified complete and in compliance with contract drawings and specifications except for non-conformances and incomplete items reported above.

<b><u>Quality Score</u></b>	5 = 100% NO problems	4 = 1 minor problems	3 = Hotspot or 2-3 minor	2 = 6+ or major problems	1 = Excessive problems
<b><u>On-Time Score</u></b>	5 = On Time	4 = Late	3 = Late by 1 day	2 = Late by 2 days	1 = Late more than 2 days
<b><u>Safety Score</u></b>	5 = 100% NO problems	4 = 1 minor problem	3 = Hotspot or 2-3 minor	2 = 4+ or major problem	1 = Injury



## LIBRARY OF INCLUDED QA/QC PLAN FORMS

### MILITARY FORMS:

- Preparatory Phase Checklist
- Initial Phase Checklist Form
- Contractor Production Report
- Contractor Quality Control Report
- Testing Plan and Log

### STANDARD FORMS:

- Point Of Contact List Form
- Project Quality Communications Plan Form
- Quality Manager Appointment Letter Form
- Project Manager Appointment Letter Form
- Superintendent Appointment Letter Form
- Project Personnel Resumes Form
- Training Plan Form
- Training Log Form
- Project Design Process Plan Form
- Design Review Form
- Controlled Materials Form
- Metals Material Receiving Inspection Report Form
- Material Inspection and Receiving Report Form
- Quality Inspection and Test Plan Form
- Test Equipment Calibration Plan and Log Form
- Quality Controlled Work Task List Form
- Daily Production Report Form
- Work Task Inspection Form
- Punch List Form
- Project License and Qualifications Form
- Project Organization Chart Form
- Project Personnel Qualification Form
- Personnel Certifications and Licenses Form
- Subcontractor And Supplier Quality Communications Plan Form
- Project Quality Training Plan Form
- Project Quality Records Plan Form
- Project Submittals Schedule and Log Form
- Project Submittal Form
- Change Order Form
- Project Design Process Plan Form
- Project Regulatory Building Codes Form

Questions? Call Ed Caldeira 410-451-8006

- Laboratory Qualification Form
- Subcontractor And Supplier Qualification Form
- Subcontractor And Supplier Certifications and Licenses Form
- Subcontractor And Supplier Quality Control Policy Requirements Form
- Project Startup Meeting Form
- Work Task Quality Assurance/Quality Control Plan Form
- Work Task Quality Control Planning Meeting Form
- Monthly Quality Control Report Form
- Inspection and Test Report Form
- Project Completion Inspection Form
- Nonconformance Report Form
- Nonconformance Report Control Log Form
- Corrective Action Report Form
- Training Record Form
- Jobsite Quality Review Planning and Log Sheet Form
- Quality System Audit Form
- System Document Control Form
- Project Records Control Form

Selected Pages

# INCLUDES REGULATORY CODES, STANDARDS, AND PERSONNEL CERTIFICATIONS

## FROM CSI DIVISIONS

- Fire Suppression - 21
- Plumbing - 22
- Utilities – 33

APPLICABLE REGULATORY CODES AND INDUSTRY STANDARDS FOR DIVISION 21 FIRE SUPPRESSION		
Description	Reference Standard No.	Reference Standard Title
Flush the piping system with potable water	NFPA 14	Standard for the Installation of Standpipes and Hose Systems
Disinfection of water mains	AWWA C651	Standard for Disinfecting Water Mains
Sprinkler system installation	NFPA 13	Standard for the Installation of Sprinkler Systems
Control and fire alarm wiring installation	NFPA 70	National Electrical Code
Installation of underground piping and fittings	NFPA 24	Standard for the Installation of Private Fire Service Mains and Their Appurtenances
Joints anchoring	NFPA 24	Standard for the Installation of Private Fire Service Mains and Their Appurtenances
Installation of High Density Polyethylene (HOPE) Piping	PIP PNSCO036	Installation of High Density Polyethylene (HOPE) Piping
Site Preparation, Excavation, and Backfill Specification	PIP CVS02100	Site Preparation, Excavation, and Backfill Specification

INSPECTION AND TESTING STANDARDS FOR DIVISION 21 FIRE SUPPRESSION		
Description	Reference Standard No.	Reference Standard Title
Hydrostatic testing	NFPA 14	Standard for the Installation of Standpipes and Hose Systems

<b>Industry-Specific Information Available by Division</b>		
<b>03 Concrete</b>	<b>08 Openings</b>	<b>27 Communications</b>
<b>04 Masonry</b>	<b>09 Finishes</b>	<b>28 Electronic Safety and Security</b>
<b>05 Metals</b>	<b>21 Fire Suppression</b>	<b>31 Earthwork</b>
<b>06 Wood Plastic Composite</b>	<b>22 Plumbing</b>	<b>32 Exterior Improvements</b>
<b>07 Thermal and Moisture Protection</b>	<b>23 HVAC</b>	<b>33 Utilities</b>
	<b>26 Electrical</b>	

Questions? Call Ed Caldeira 410-451-8006



For More Information:

Contact: Ed Caldeira

410-451-8006

[www.firsttimequality.com](http://www.firsttimequality.com)

[EdC@FirstTimeQuality.com](mailto:EdC@FirstTimeQuality.com)

For More Information, contact: Ed Caldeira • Caldeira Quality, LLC • First Time Quality<sup>SM</sup>

410-451-8006 • [www.firsttimequality.com](http://www.firsttimequality.com) • [EdC@FirstTimeQuality.com](mailto:EdC@FirstTimeQuality.com)