



<b>BODY</b> 110' Single Axle Platform Aluminum Body PUC <b>COMPT, DRIVER SIDE FRONT</b> Full Height RollUp Forward <b>COMPT, DRIVER SIDE REAR</b> Full Height RollUp Rearward <b>COMPT, PASSENGER SIDE FRONT</b> Full Height RollUp Forward <b>COMPT, PASSENGER SIDE REAR</b> Full Height RollUp Rearward	<b>WATER TANK</b> 470 Gallon Poly Water Tank <b>Foam System</b> Husky 3 Single Agent Foam System <b>Foam Cell</b> 30 Gallon Foam Cell, Reduced Water, PUC
--	--

<b>CHASSIS</b> Enforcer Chassis, PUC <b>ENGINE</b> 450 HP Cummins L9 Engine	<b>CAB</b> 7000 Enforcer Cab, PUC <b>BUMPER</b> 19" Extended Stainless Steel	<b>AXLE, FRONT, CUSTOM</b> 22,800 Lb Dana Axle <b>AXLE, REAR</b> 33,500 Lb Meritor Axle	<b>TRANSMISSION</b> Allison 5th Gen, 3000 EV5 P	<b>PUMPHOUSE</b> Control Zone, PAL/PAP PUC <b>PUMP</b> 1500 GPM Pierce PUC	<b>CROSSLAYS, 1.50"</b> (2) 1.50", Poly Trays, 200' <b>CROSSLAYS, 2.50"</b> (1) 2.50", Poly Tray, 150'	<b>SPEEDLAYS</b> Speedlays Not Required <b>GENERATOR</b> Harrison BkW MAS-D Hydraulic
--	---	--	--	---	---	--

		JOB NO. 32001 SCALE 1:24 DATE
TITLE MAKE MODEL ENFORCER	FOR TABER FIRE DEPARTMENT TABER, ALBERTA, CANADA	DRAWN BY TKA CHECKED BY CRI SHEET NO. 1 OF 1
DWG NO. 32001AD		DATE BY CH

NOTE: DIMENSIONS SHOWN ARE APPROXIMATE AND ARE SUBJECT TO MINOR DEVIATIONS AS MAY OCCUR OR BE NECESSARY IN CONSTRUCTION. MINOR DETAILS NOT SHOWN.

1. ONE 1.50" OUTLET WITH 2.00" PIPING AND SWIVEL LOCATED IN CENTER BUMPER TRAY  
 2. AIR INLET WITH DISCONNECT COUPLING LOCATED IN THE DRIVER SIDE STEP WELL  
 3. SHORELINE RECEPTACLE WITH KOSMOSL SUPER AUTO-EJECT LOCATED IN THE DRIVER SIDE STEP WELL  
 4. BATTERY CHARGER LOCATED IN COMPARTMENT D3  
 5. BATTERY CHARGE INDICATOR LOCATED ON THE DRIVER SIDE SEAT RISER  
 6. NINE ADJUSTABLE SHELVES IN COMPARTMENTS PER SHOP ORDER  
 7. THREE FLOOR MOUNTED SLIDE-OUT TRAYS IN COMPARTMENTS PER SHOP ORDER  
 8. ONE SWING-OUT TOOL BOARD WITH PEGBOARD PATTERN IN COMPARTMENT PER SHOP ORDER  
 9. ONE ALUMINUM PEGBOARD WITH TRACKS ON THE SIDE WALLS OF COMPARTMENT PER SHOP ORDER  
 10. FOUR 15/20A 120V RECEPTACLES IN COMPARTMENTS PER SHOP ORDER  
 11. CIRCUIT BREAKER PANEL IN COMPARTMENT D4  
 12. NON-RAISED AERIAL PEDestal  
 13. 1250 GPM HIGH FLOW WATERWAY  
 14. AERIAL WIRELESS REMOTE CONTROL  
 15. REMOTE MONITOR CONTROLS AT PUMP PANEL