

FAI/04-26

***THERMAL ANALYSIS OF KE-KW TRANSFER LINE AND
STAGING AT K WEST BASINS***

Submitted To:

BNFL, Inc.
Richland, Washington

Prepared By:

Martin G. Plys and Sung Jin Lee

Fauske & Associates, LLC
16W070 West 83rd Street
Burr Ridge, Illinois 60527
TEL: (630) 323-8750
FAX: (630) 986-5481

August 2004

TABLE OF CONTENTS

	<u>Page</u>
LIST OF FIGURES	iv
LIST OF TABLES	v
1.0 SUMMARY	1-1 of 1-2
2.0 SCOPE AND PURPOSE	2-1 of 2-1
3.0 PROCESS REFERENCE DESCRIPTION AND PARAMETERS	3-1 of 3-7
3.1 Process Reference Description	3-1
3.2 Process Design Parameters	3-7
3.3 Acceptance Criteria	3-7
4.0 SLUDGE AND PROCESS MODELS	4-1 of 4-13
4.1 HANSF Computer Code	4-1
4.2 KE-KW Transfer Line Modeling	4-2
4.3 Transfer Line Pit Box Model	4-2
4.4 Consolidation Container Model	4-3
4.5 Sludge Properties	4-9
4.6 Boundary Conditions and Parameters	4-10
4.7 Input File Summary	4-10
4.8 Stratification of Sludge	4-11
4.9 Sludge Inventory Summary	4-12
5.0 CALCULATION CASE DESCRIPTION	5-1 of 5-3
6.0 KE-KW TRANSFER RESULTS	6-1 of 6-2
7.0 STAGING AT K WEST BASINS	7-1 of 7-2

TABLE OF CONTENTS

(concluded)

	<u>Page</u>
8.0 RESULTS, CONCLUSIONS, AND DISCUSSION SUMMARY	8-1 of 8-5
8.1 Results Summary	8-1
8.2 Conclusions	8-1
8.3 Discussion	8-2
8.3.1 Thermal Stability Margin	8-2
8.3.2 Flammable Gas Considerations	8-3
8.3.3 Likely Hydrogen Generation Rates	8-4
9.0 GAS RETENTION	9-1 of 9-X
10.0 REFERENCES	10-1 of 10-2
APPENDIX A HANSF and HADCRT Computer Code Description	A-1 of A-5
APPENDIX B Calculation Notes for HANSF/SLUDGE Input	B-1 of B-22
APPENDIX C Thermal Issues for Sludge Line Transfer	C-1 of C-17
APPENDIX D HANSF/SLUDGE Input Files	D-1 of D-36
APPENDIX E KE-KW Transfer History Plots	E-1 of E-5
APPENDIX F K West Staging Transient History Plots	F-1 of F-10
APPENDIX G Quality Assurance Documentation	G-1 of G-13

LIST OF FIGURES

<u>Figure</u>		<u>Page</u>
3-1	KE to KW Transfer Process	3-2
3-2	Hose-in-Hose Cross-Section	3-3
3-3	Pump Pit Box Layout	3-4
3-4	KW Sludge Consolidation Container	3-5
3-5	KW Basin Container Arrangement	3-6
4-1	Nodalization for KE-KW Stagnant Line	4-4
4-2	Nodalization for KE-KW Plugged Line	4-5
4-3	Nodalization for Transfer Line Pit Box Spill	4-6
4-4	K West Consolidation Container Sludge Nodalization.....	4-8
9-1	Need Title	9-X
9-2	Need Title	9-X
9-3	Need Title	9-X
C-1	Sludge Heat Up Due to Insolation	C-9

LIST OF TABLES

<u>Table</u>		<u>Page</u>
4-1	Sludge Quantities Modeled	4-13
5-1	Initial and Boundary Conditions and Key Outputs	5-1
5-2	Case Matrix	5-2
8-1	Results Summary	8-1
9-1	Need Title	9-X
B.1	Transfer Line Dimensions and Operation Parameters	B-1
B.2	Thermal Properties of Hose-in-Hose	B-3
B.3	Pump Pit Box Dimensions	B-3
B.4	Thermal Properties of Pump Pit Box Wall	B-4
B.5	KW Consolidation Container Dimensions	B-4
B.6	Insolation Data for Latitude 46°N – Horizontal Surface Facing Up	B-5
B.7	Peak Hanford Ambient Air Temperatures	B-5
B.8	KE Basin Safety-Basis Floor and Canister Sludge Parameters	B-6
B.9	Stratified 80/20 Mixture Properties – U Metal Segregated to Bottom 35%	B-7
B.10	HADCRT Region Inputs	B-13
B.11	HADCRT Inputs for Sludge Heat Conductor	B-14
B.12	HADCRT Inputs for Sidewall Heat Conductors	B-15
B.13	HADCRT Inputs for Container Bottom Heat Conductor	B-16
C.1	KE Basin Safety-Basis Floor and Canister Sludge Parameters	C-3

LIST OF TABLES

(concluded)

<u>Table</u>		<u>Page</u>
C.2	Decay, Reaction, Solar, and Pump Heat Sources in Diluted Sludge at Different Sludge Temperatures	C-5

