



**Timberland Door, LLC**  
12555 Enterprise Boulevard  
Largo, FL 33773  
Phone: 727-539-8600  
Fax: 727-539-8610  
www.timberlanddoor.com

---

## Architectural Specifications

### Section 08215

#### Solid Core MDF Doors

#### Part 1 – General

##### 1.01 Summary

- A. Section includes:
  - 1. Solid Core MDF Doors
  - 2. Factory Priming & Pre-machining
  - 3. Solid Core MDF Bi-Fold doors and hardware
- B. Related Sections:
  - 1. Section 01300 – Submittals
  - 2. Section 01600 – Materials and Equipment
  - 3. Section 06200 – Finish Carpentry
  - 4. Section 06275 – Custom Wood Door Frames
  - 5. Section 08110 – Steel Wood Door Frames
  - 6. Section 08710 – Door Hardwar
  - 7. Section 09900 – Painting

##### 1.02 References

- A. American Society for Testing and Materials (ASTM)
  - 1. ASTM A208.2-94, A208.1-99  
Standard Methods for Evaluation the Properties of Wood-Based Fiber and Particle Board Panel Materials

##### 1.03 Submittals

- A. Shop Drawings – Submit in accordance with Section 01300. Indicated location size, elevation, details of construction, and factory preparation requirements for each door type.
- B. Templates – Hardware templates for hardware mounted on doors will be submitted under Section 08710 directly to door manufacturer immediately after acceptance of hardware schedule. Report failure to receive templates with reasonable promptness to General Contractor.
- C. Quality Control Submittals
  - a. Warranty – Submit in accordance with Section 01700



**Timberland Door, LLC**  
12555 Enterprise Boulevard  
Largo, FL 33773  
Phone: 727-539-8600  
Fax: 727-539-8610  
[www.timberlanddoor.com](http://www.timberlanddoor.com)

---

## **Architectural Specifications**

### **1.04 Delivery, Storage and Handling**

A. General – Comply with Section 01600 (Material and Equipment)

1. Delivery – Do not deliver doors to building until entirely enclosed, drywall, plaster and concrete work is completed and dry, and humidity in the building has reached average relative humidity of the location
2. Storage – Stack doors flat and off the floor on a level surface in a dry, well ventilated area. Keep doors covered while allowing air circulation.
3. Handling – Handle doors very carefully, and do not drag doors across one another
4. Protection – Do not subject doors to abnormal heat, dryness, humidity or drastic changes in these conditions. Allow sufficient time for doors to acclimate to average existing conditions of the area before installation.

### **1.05 Warranty**

A. Timberland Door MDF doors are warranted for internal use only

## **Part 2 – Products**

### **2.01 Manufacturers**

A. Acceptable Manufacturers – Timberland Door, 12555 Enterprise Blvd., Largo, FL 33773