

Connection details & information shown on this drawing are for approval of positions only. Connections are not included unless they are specifically detailed on your order and our final agreed quotation.


Copyright in all design and detail is reserved by Dutypoint systems and these drawings must not be reproduced without written permission.

Tank Foundations

BS EN 13280:2001 (E) ANNEX M.2

The top surface of the foundation, whether it is flat screed concrete, steelwork, support walls or pillars, should be flat, level and free from any local irregularities. It should not vary more than 2mm in any 1m, or a total of 6mm in any 6m, measured laterally or diagonally. Intermittent supports should be spaced in accordance with the manufacturer's instructions and should be continuous in one direction.

If foundations are to be provided by suspended floors or beams, then the foundation should be constructed so that when the tank is full, the combined deflections should not exceed 1/500th of the span.



ISSUE STATUS	ISSUE DATE
FOR APPROVAL	15/05/2014
W/D No ENQ	
TITLE G/A OF 1380 X 1040 X 1500 GRP ONE PIECE SPECIAL TANK	
DRN JPC	DATE 15/05/2014
SCALE 1:25	DRG No DPT5607
FOR : DUTYPOINT SYSTEMS	
PROJECT : SCUBA 1650 (AB)	