





Hudson Run Road Bridge

Summit County, Ohio

Overview

This bridge is located in an industrial area with heavy truck traffic. The bridge deck consisted of 17 prefabricated panels. The panels were installed in one day; with a second day for connection of the deck to girders; and finishing Deck Weight: 21 psf on a third day of panel-to-panel sealing.

Owner: Summit County, Ohio Installation Date: October 2006

Bridge Deck Dimensions

Deck Size: 117.8 feet by 34 feet Deck Area: 4,005 square feet

Deck Panel Dimensions: 8.3 feet by 34 feet

Deck Depth: 7.7 inches





Bridge Features

Requirements:

• HS-25 Vehicle; L/400 deflection

Superstructure: Steel girders Beam Spacing: 7 feet-2 inches

Deck to Beam Connection: Bolted to welded

shear studs

Special Requirements: None

Guard Rail: Attached to steel superstructure

Non-Slip Overlay: Asphalt

Color: Gray