

Complete Corrosion Control.

## WPN WET PIPE NITROGEN INERTING

### **Project Case Study - Florida Regional Mall**

Project Type:	Large Warehouse Facility	
Location:	Florida, USA	
Sprinkler Systems:	1.19 million sq. ft. of gross leasable space, 36 wet pipe fire sprinkler systems	
Nitrogen Introduced:	December, 2012	Ir



Iron Oxide Deposits on Bottom of Main

Wet pipe fire sprinkler systems in malls are especially susceptible to accelerated corrosion rates because systems are drained and refilled frequently for tenant modification projects. The process adds fresh oxygen with each drain and refill cycle. A large regional mall in Tampa, Florida was experiencing one leak per month on its wet pipe fire sprinkler systems. The ECS Wet Pipe Nitrogen Inerting (WPNI) process designed specifically to prevent oxygen corrosion in wet pipe systems was used to stop the leaks.

#### **History and Background**

- Mall opened 2001 11 years old when work commenced
- Large, two level, regional mall located in Southern Florida
- 1.19 million sq. ft. of gross leasable space
- 36 wet pipe fire sprinkler systems protect the tenant and common mall areas – anchor stores are served by separate systems not included in this study
- Electric fire pump supplied by municipal water fed the overhead bulk supply loop feeding system risers located in service corridors around the perimeter of the building



Exterior Leak on 6" Main

Fire sprinkler piping materials:

- Black steel schedule 10 mains
- Black steel cross mains and branch lines a mix of schedule 10 and 40

#### **Project Background**

- The mall was experiencing multiple leaks on a monthly basis
- 36 wet systems were nitrogen inerted in December 2012
- Pipe replacement limited to repair of existing leaks
- Only one leak since nitrogen inerting the wet pipe zones

#### **Corrosion related leak history:**

- Leaks occurring in wet pipe branch lines and mains on a monthly basis
- Leaks occurred in tenant spaces and common mall areas
- Merchandise damage risk due to fire sprinkler water leak



Weld Seam Corrosion Leak

Engineered Corrosion Solutions • 11336 Lackland Road • St. Louis, MO 63146 • Phone 314-432-1377 • ecscorrosion.com



Complete Corrosion Control.

# WPN WET PIPE NITROGEN INERTING

#### **Preliminary Assessment Work**

Based on the history of leaks occurring in the facility, Engineered Corrosion Solutions was contracted to identify the root cause of the corrosion and develop a corrosion control strategy to prevent future leaks. The conclusion was that trapped air in the high points of the mains and branch lines resulted in oxygen corrosion of the piping. Oxygen corrosion resulted in the formation of iron oxide deposits in the system piping, further accelerating the metal loss and resulting in additional leaks. The recommended method of preventing additional metal loss and leaks was to remove oxygen from the sprinkler system by using nitrogen gas to inert the piping.



**ECS Nitrogen Inerting Vent** 

#### Implementation of ECS Wet Pipe Nitrogen Inerting (WPNI)

- No significant pipe replacement was performed, existing leaks were addressed
- Installation of ECS Protector Nitrogen Inerting Vents on each of the 36 wet pipe systems
- Installation of ECS Protector Nitrogen Injection Ports on each of the 36 wet pipe risers
- Performed WPNI on all of the fire sprinkler systems using the ECS nitrogen inerting protocol for wet pipe fire sprinkler systems
- Maintained inert state during subsequent drains and refills of the systems following specific ECS protocols

#### **Results and Conclusions**

In late December, 2012, the ECS nitrogen inerting equipment was installed on the 36 wet pipe zones protecting the common mall areas and tenant spaces. ECS was onsite with the mall facilities personnel and fire sprinkler contractor to deploy the nitrogen inerting procedures. To ensure that the proper inerting protocols were followed, the mall owner dictated that the primary fire sprinkler contractor must *always* be onsite for any drain downs of the system. Even if another contractor performed any work in the facility, the primary contractor was present to perform the draining and refilling protocols to maintain the nitrogen inerted state on the systems.

Since the initial inerting of the 36 wet pipe systems the mall has only experienced <u>one leak</u>. The fire sprinkler contractor referred to WPNI as the *'miracle cure'* that has completely resolved the mall's corrosion issues.



Pressurized Cylinders Provide Nitrogen Gas

Engineered Corrosion Solutions • 11336 Lackland Road • St. Louis, MO 63146 • Phone 314-432-1377 • ecscorrosion.com